drone-spot


FLIGHT CARD

Generated on 21 November 2026

Aincourt Sanatorium

Heritage · Val-d'Oise

GPS coordinates	49.07726, 1.75601
Elevation	180 m
Maximum height	50 m max
Access	On foot < 1,000 m
Nearest aerodrome	Mantes Chérence Airfield (LFFC) 4.8 km W · spot 24 m higher
Spot reference	305001



Spot location and restrictions (Drone-Spot map image)

Sun (local times, UTC+01:00)

Day	Dawn	Sunrise	Sunset	Dusk	Day length	Golden hour
Sat 21 Nov	07:37	08:12	17:06	17:41	8 h 53	08:12–09:03 · 16:14–17:06
Sun 22 Nov	07:38	08:13	17:05	17:40	8 h 51	08:13–09:05 · 16:13–17:05
Mon 23 Nov	07:39	08:15	17:04	17:39	8 h 49	08:15–09:07 · 16:12–17:04

Nearby aerodromes

Aerodrome	Type	Distance	Elevation
Mantes Chérence Airfield	Aerodrome	4.8 km W	156 m
Base Paramoteurs d' Avernes	Aerodrome	9.5 km E	139 m
Centre Hospitalier F. Quesnay Heliport	Heliport	11 km SW	28 m
Flins Heliport	Heliport	13 km SE	25 m

Description

The Aincourt sanatorium was a treatment center specialized in pulmonary tuberculosis (phthisis), located in the village of Aincourt (Val-d'Oise department) in France. The sanatorium, currently located in the Vexin français regional natural park, was built by the architects Édouard Crevel and Paul Decaux between 1931 and 1933. It is one of the largest complexes of its kind built in the 20th century. It was also a concentration camp between 1940 and 1942. The building is currently partly occupied by the Vexin intercommunal hospital group. It has been listed as a historic monument since 1 February 1999.

Scan to open the up-to-date spot page: weather, map and restrictions.

https://www.drone-spot.tech/en/fiche-spot.aspx?id=305001

Before every flight: check the UAS zones map, NOTAMs and temporary areas, the weather and the Kp index.

Preparing the flight

Pre-flight Check-List

- ☐ Area checked: UAS zones, restrictions, protected areas
- ☐ NOTAMs and temporary areas checked
- ☐ Weather: wind, gusts, rain, visibility; Kp index
- ☐ Operator number displayed on the drone
- ☐ Training certificate or licence with me
- ☐ Third-party liability insurance checked
- ☐ Batteries charged: drone, controller, phone
- ☐ Propellers, motors and frame in good condition
- ☐ Memory card inserted and empty
- ☐ Software up to date, compass and IMU calibrated
- ☐ Return to home: home point and return height set
- ☐ Electronic signalling or remote ID active
- ☐ Take-off area clear, people informed and at a distance
- ☐ Observer present for FPV flights

Key rules of the open category

Recreational flying in France: European open-category rules, applied by the DGAC.

- Maximum height: 120 m above the ground, lower where a restriction requires it.
- Always keep the drone in sight; when flying FPV, an observer keeps it in sight next to you.
- Never fly over crowds and keep the distances of your subcategory (A1, A2 or A3).
- Respect UAS geographical zones: around aerodromes, prohibited or restricted areas, protected areas, sensitive sites.
- Register as an operator if the drone weighs 250 g or more or carries a camera (toys excepted), and display the number on the drone.
- Training: online A1/A3 certificate from 250 g or for a class C1 drone; A2 certificate to fly closer to people with a class C2 drone.
- Always give way to manned aircraft and land if one approaches.
- Respect privacy: no images that identify people without their consent; aerial photography is prohibited in some areas.
- Check your third-party liability insurance.
- In France: registration and training on AlphaTango (DGAC); a drone of 800 g or more must broadcast electronic signalling (or the remote ID of class-marked drones).

Non-exhaustive summary: rules change. Reference: the DGAC open-category guide and the country's regulations.

Useful links

UAS zones map around the spot : https://www.drone-spot.tech/en/carte-uas.aspx?lat=49.07726&lon=1.75601
Drone pilot library : https://www.drone-spot.tech/en/bibliotheque
DGAC open-category guide (French) : https://www.drone-spot.tech/en/bibliotheque/guide-categorie-ouverte
Registration and training (AlphaTango) : https://alphatango.aviation-civile.gouv.fr
NOTAMs and temporary areas (SOFIA Briefing) : https://sofia-briefing.aviation-civile.gouv.fr

My flight notes

Information sheet generated by Drone-Spot from community data: it replaces neither official aeronautical information nor the regulations. The remote pilot remains responsible for the flight.