drone-spot


FLIGHT CARD

Generated on 21 November 2026

Simiane la Rotonde, Notre Dame de Pitié chapel

Heritage · Alpes-de-Haute-Provence

GPS coordinates	43.98249, 5.55787
Elevation	758 m
Maximum height	50 m max
Access	Direct access by car
Nearest aerodrome	Altisurface de Banon 12 km NE · spot 377 m lower
Spot reference	307857



Spot location and restrictions (Drone-Spot map image)

Sun (local times, UTC+01:00)

Day	Dawn	Sunrise	Sunset	Dusk	Day length	Golden hour
Sat 21 Nov	07:09	07:40	17:07	17:38	9 h 26	07:40–08:25 · 16:22–17:07
Sun 22 Nov	07:10	07:42	17:06	17:38	9 h 24	07:42–08:26 · 16:21–17:06
Mon 23 Nov	07:11	07:43	17:05	17:37	9 h 22	07:43–08:28 · 16:20–17:05

Nearby aerodromes

Aerodrome	Type	Distance	Elevation
Altisurface de Banon	Aerodrome	12 km NE	1,135 m
Saint Martin de Castillon	Aerodrome	14 km S	335 m
Hôtel La Coquillade Heliport	Heliport	22 km SW	249 m

Description

Data What is there to say about this building? The date 1635 is carved on its lintel, but this is only a repair, as the archives suggest it is much older. It is first described in a 1859 text as being located outside the walls, in the Moulins district. An 1906 inventory then states that the chapel was built by the Pélissier des Granges family, who had established their burial place there. Finally, another document mentions an old text by Abbé Corriol, which provides a notarial deed dated 1573 and estimates that it dates back to the 16th century. There was indeed a Jean Pélissier, born around 1566 in Simiane and died in 1628, who was bishop of Apt from 1607 until his death. The chapel could therefore have belonged to his family. The function of the remains of the adjoining building is unknown, but one of the stones of its doorway jambs is cut in a curve, indicating the reuse of an old …

Scan to open the up-to-date spot page: weather, map and restrictions.

https://www.drone-spot.tech/en/fiche-spot.aspx?id=307857

Before every flight: check the UAS zones map, NOTAMs and temporary areas, the weather and the Kp index.

Preparing the flight

Pre-flight Check-List

- ☐ Area checked: UAS zones, restrictions, protected areas
- ☐ NOTAMs and temporary areas checked
- ☐ Weather: wind, gusts, rain, visibility; Kp index
- ☐ Operator number displayed on the drone
- ☐ Training certificate or licence with me
- ☐ Third-party liability insurance checked
- ☐ Batteries charged: drone, controller, phone
- ☐ Propellers, motors and frame in good condition
- ☐ Memory card inserted and empty
- ☐ Software up to date, compass and IMU calibrated
- ☐ Return to home: home point and return height set
- ☐ Electronic signalling or remote ID active
- ☐ Take-off area clear, people informed and at a distance
- ☐ Observer present for FPV flights

Key rules of the open category

Recreational flying in France: European open-category rules, applied by the DGAC.

- Maximum height: 120 m above the ground, lower where a restriction requires it.
- Always keep the drone in sight; when flying FPV, an observer keeps it in sight next to you.
- Never fly over crowds and keep the distances of your subcategory (A1, A2 or A3).
- Respect UAS geographical zones: around aerodromes, prohibited or restricted areas, protected areas, sensitive sites.
- Register as an operator if the drone weighs 250 g or more or carries a camera (toys excepted), and display the number on the drone.
- Training: online A1/A3 certificate from 250 g or for a class C1 drone; A2 certificate to fly closer to people with a class C2 drone.
- Always give way to manned aircraft and land if one approaches.
- Respect privacy: no images that identify people without their consent; aerial photography is prohibited in some areas.
- Check your third-party liability insurance.
- In France: registration and training on AlphaTango (DGAC); a drone of 800 g or more must broadcast electronic signalling (or the remote ID of class-marked drones).

Non-exhaustive summary: rules change. Reference: the DGAC open-category guide and the country's regulations.

Useful links

UAS zones map around the spot : https://www.drone-spot.tech/en/carte-uas.aspx?lat=43.98249&lon=5.55787
Drone pilot library : https://www.drone-spot.tech/en/bibliotheque
DGAC open-category guide (French) : https://www.drone-spot.tech/en/bibliotheque/guide-categorie-ouverte
Registration and training (AlphaTango) : https://alphatango.aviation-civile.gouv.fr
NOTAMs and temporary areas (SOFIA Briefing) : https://sofia-briefing.aviation-civile.gouv.fr

My flight notes

Information sheet generated by Drone-Spot from community data: it replaces neither official aeronautical information nor the regulations. The remote pilot remains responsible for the flight.